

Phone: (916) 442-5400  
 Fax: (916) 520-6966

**Proposal:** NC23 062  
**Date:** 4/5/2023

<b>To:</b> City of Placerville Attn: Other	<b>Project:</b> 48 Inch Dist 3 Culvert Rehab Placerville, CA
--	--

<b>Salesperson</b>		
William Bonney		

**Scope of Work**

- The prices stated in this proposal include:
1. One mobilization and demobilization. - based on a mutually agreeable schedule between Nor Cal Pipeline and the Prime Contractor. The Prime Contractor needs to give Nor Cal Pipeline at least one-week advance notice of any changes to the mutually agreed upon schedule. If through no fault of Nor Cal Pipeline the mutually agreed upon schedule changes with less than one-week notice, then Nor Cal Pipeline may charge the Prime Contractor an additional mobilization charge and any potential lost materials including but not limited to tube already "wetout".
  2. If at no fault of Nor Cal the project is delayed and remob is required; an additional mobilization charge of \$5000.00 will be incurred.
  3. Pipeline cleaning. Loose debris and "normal" deposits only. Extraordinary conditions will need to be treated as a point repair.
  4. Pre-Video inspections and documentation of existing pipe prior to reconstruction with the Nor Cal Pipeline process for pipe rehabilitated by CIPP.
  5. Installation of Cured-In-Place Pipe (CIPP) lining per Specification Section Cured-In-Place Pipe Lining including inversion, curing, and finishing. Nor Cal Pipeline will utilize a polyester
  6. Internal lateral reinstatement using our internal Lateral Cutter.
  7. Post video inspection following completion of the installation to document your new pipe rehabilitated by CIPP.
  8. Confined space safe entry practices.
  9. Prevailing Wages for the State of California. Nor Cal Pipeline Services is Signatory to the Laborers and Operators Union.
  10. Prices are good for 90 Days
  11. One-year standard construction warranty.
  12. Certificate of insurance with a standard coverage.
  13. Use tax on materials and equipment rental.

**Exclusions**

Not included in the prices stated in this estimate are costs associated with the items listed below. These items, if needed or found to be applicable, would be provided by NOR CAL PIPELINE at your additional cost; or would be furnished by others, at your direction, at no cost to NOR CAL PIPELINE:

1. Point repairs if required prior to lining
2. Traffic Control
3. Water Source (Access to Water provided by Prime Contractor)
4. If preliminary video inspection of the pipe interior indicates excessive damage, or other extra-ordinary condition, which will require excavation, or other extraordinary remedy, to prepare the pipe for installation of the Insitutube, then those services will be provided by the Prime Contractor or Owner. This will include excessive roots, excessive debris, and protruding taps.
5. Additional cleaning and televising mobilizations and/or setups due to point repairs, obstruction removals, or delays out of our control will be an additional charge.
6. Active lateral verification, other then visual inspection.
7. Water from fire hydrants within a convenient distance from each cleaning and inversion site location.
8. Legal dumpsite for debris resulting from pipe cleaning.
9. If any hazardous or toxic materials are encountered during the project, the Owner will be responsible for the removal

# Proposal



and disposal of the materials.

10. Bypass pumping of mainlines and of any laterals that may be required
11. Installation of cleanouts, or other ports, if required for special bypass pumping requirements for businesses.
12. Styrene Air Monitoring and/or Styrene Soil Testing
13. Removal of ratwalk
14. Nightwork (These Prices assume Day Rates)
15. Manhole installation, rehabilitation, and/or replacement, if required.
16. Site restoration.
17. Project permits and/or local licenses.
18. Additional premiums for special insurance coverage(s) demanded by you or other parties particular to this project.
19. Performance and Payment Bond not included. This is available upon request, but if required please add 2.5% to the total project cost.
20. Additional taxes not specifically listed in inclusions.

Reference	Description	Quantity	UOM	Unit Price	Extended Price
01	Mobilization	1.0000	LS	10,000.0000	<b>10,000.00</b>
02	CIPP Line 48" CMP Pipe	307.0000	LF	515.0000	<b>158,105.00</b>

<b>Proposal Total:</b>	<b>168,105.00</b>
------------------------	-------------------

<b>Acceptance</b>	
Accepted by:	_____
Title:	_____
Date:	_____