

Road Construction Emissions Model, Version 9.0.0

Daily Emission Estimates for -> Clay Street Bridge Replacement Project														
Project Phases (Pounds)	ROG (lbs/day)	CO (lbs/day)	NOx (lbs/day)	Total PM10 (lbs/day)	Exhaust PM10 (lbs/day)	Fugitive Dust PM10 (lbs/day)	Total PM2.5 (lbs/day)	Exhaust PM2.5 (lbs/day)	Fugitive Dust PM2.5 (lbs/day)	SOx (lbs/day)	CO2 (lbs/day)	CH4 (lbs/day)	N2O (lbs/day)	CO2e (lbs/day)
Grubbing/Land Clearing	0.59	12.43	1.89	10.10	0.10	10.00	2.15	0.07	2.08	0.02	2,233.23	0.57	0.08	2,270.25
Grading/Excavation	2.87	57.10	6.41	10.36	0.36	10.00	2.37	0.29	2.08	0.10	9,562.38	2.85	0.15	9,677.37
Drainage/Utilities/Sub-Grade	1.58	33.41	3.92	10.25	0.25	10.00	2.27	0.19	2.08	0.06	5,657.79	1.16	0.09	5,714.38
Paving	0.77	18.54	2.24	0.14	0.14	0.00	0.09	0.09	0.00	0.03	2,895.43	0.74	0.08	2,939.01
Maximum (pounds/day)	2.87	57.10	6.41	10.36	0.36	10.00	2.37	0.29	2.08	0.10	9,562.38	2.85	0.15	9,677.37
Total (tons/construction project)	0.26	5.25	0.61	1.16	0.04	1.12	0.26	0.03	0.23	0.01	878.86	0.24	0.02	889.28

Notes:		Project Start Year ->	2025
		Project Length (months) ->	12
		Total Project Area (acres) ->	1
		Maximum Area Disturbed/Day (acres) ->	1
		Water Truck Used? ->	Yes
		Total Material Imported/Exported Volume (yd ³ /day)	
		Daily VMT (miles/day)	
Phase	Soil	Asphalt	Soil Hauling Asphalt Hauling Worker Commute Water Truck
Grubbing/Land Clearing	0	33	0 60 160 40
Grading/Excavation	1	8	30 30 600 40
Drainage/Utilities/Sub-Grade	0	9	0 30 600 40
Paving	0	22	0 60 400 40

PM10 and PM2.5 estimates assume 50% control of fugitive dust from watering and associated dust control measures if a minimum number of water trucks are specified.
 Total PM10 emissions shown in column F are the sum of exhaust and fugitive dust emissions shown in columns G and H. Total PM2.5 emissions shown in Column I are the sum of exhaust and fugitive dust emissions shown in columns J and K.
 CO2e emissions are estimated by multiplying mass emissions for each GHG by its global warming potential (GWP), 1, 25 and 298 for CO2, CH4 and N2O, respectively. Total CO2e is then estimated by summing CO2e estimates over all GHGs.

Total Emission Estimates by Phase for -> Clay Street Bridge Replacement Project														
Project Phases (Tons for all except CO2e. Metric tonnes for CO2e)	ROG (tons/phase)	CO (tons/phase)	NOx (tons/phase)	Total PM10 (tons/phase)	Exhaust PM10 (tons/phase)	Fugitive Dust PM10 (tons/phase)	Total PM2.5 (tons/phase)	Exhaust PM2.5 (tons/phase)	Fugitive Dust PM2.5 (tons/phase)	SOx (tons/phase)	CO2 (tons/phase)	CH4 (tons/phase)	N2O (tons/phase)	CO2e (MT/phase)
Grubbing/Land Clearing	0.01	0.16	0.02	0.13	0.00	0.13	0.03	0.00	0.03	0.00	29.48	0.01	0.00	27.19
Grading/Excavation	0.17	3.39	0.38	0.62	0.02	0.59	0.14	0.02	0.12	0.01	568.01	0.17	0.01	521.49
Drainage/Utilities/Sub-Grade	0.06	1.32	0.16	0.41	0.01	0.40	0.09	0.01	0.08	0.00	224.05	0.05	0.00	205.29
Paving	0.02	0.37	0.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	57.33	0.01	0.00	52.79
Maximum (tons/phase)	0.17	3.39	0.38	0.62	0.02	0.59	0.14	0.02	0.12	0.01	568.01	0.17	0.01	521.49
Total (tons/construction project)	0.26	5.25	0.61	1.16	0.04	1.12	0.26	0.03	0.23	0.01	878.86	0.24	0.02	806.75

PM10 and PM2.5 estimates assume 50% control of fugitive dust from watering and associated dust control measures if a minimum number of water trucks are specified.
 Total PM10 emissions shown in column F are the sum of exhaust and fugitive dust emissions shown in columns G and H. Total PM2.5 emissions shown in Column I are the sum of exhaust and fugitive dust emissions shown in columns J and K.
 CO2e emissions are estimated by multiplying mass emissions for each GHG by its global warming potential (GWP), 1, 25 and 298 for CO2, CH4 and N2O, respectively. Total CO2e is then estimated by summing CO2e estimates over all GHGs.
 The CO2e emissions are reported as metric tons per phase.