



City of Placerville

Engineering Department
3101 Center Street
Placerville, CA 95667
Phone: (530) 642-5250

ADDENDUM NUMBER 1

Dated: June 16, 2026

**to the
Notice to Bidders, Special Provision, Proposal and Contract Documents
for Construction of**

**GIOVANNI ROAD SEWER LINE REPLACEMENT
PROJECT NO. 42224
City of Placerville**

Bids Due: Thursday, June 18, 2026; 2:00 p.m.

This Addendum is issued to the Giovanni Road Sewer Line Replacement Project. Submit proposals for this work with the understanding and full consideration of this Addendum. The revisions declared in this Addendum are essential parts of the Contract.

Bidders are also directed to sign this Addendum as acknowledged, and attach the complete, signed Addendum to the Proposal.

The following responses to questions asked to date:

Question No. 1: Is there a staging area being provided by the City?

Answer: No staging area will be provided by the City for this project. There are easements located along the project area that may be suitable for staging. The lift station fence gate may be opened to provide additional staging area, but the lift station wet well location could prevent equipment from driving in and out.

Question No. 2: Is there City property to stage nearby the worksite?

Answer: Approximately 0.8 miles away is Immigrant Ravine Rd which is an undeveloped City owned property which may be used for staging so long as the site is appropriately stabilized before, during, and after the project.

Question No. 3: What about the gate in the backyard of 2413 Patton Court?

Answer: The City is not obligated to keep the gate clear. The owner has been previously informed not to use the easement to access their property as the easement is for the sewer lift station and not for public use.

Question No. 4: Is 2445 Giovanni on a residential sewer pump?

Answer: Yes, the city recommends that the contractor coordinate with the property owner to deactivate the pump during the sewer construction.

Question No. 5: What is a modified trash rack?

Answer: A modified trash rack consists of a flared end section (Caltrans STD DWG D94A) with a custom made or off-the-shelf trash rack conforming to Sacramento County STD DWG 9-26G.

Question No. 6: Will the sewer pipe require pressure tests?

Answer: No, pressure test of the sewer pipe will not be required due to a live sewer lateral connection that will need to be re-connected near the lift station. Final video inspection is still required per project specification 77-5.06.

Question No. 7: Will the new sewer manhole need to be vacuum tested?

Answer: Vacuum testing is required per project specification 77-5.06.

The following changes are made to the project plans, Notice to Bidders, Special Provisions, Proposal, and contract as part of this addendum:

Item No. 1: Change the pipe size for the 6' stub-out at upstream of the new sewer manhole from 4" to 6".

Item No. 2: Change the pipe size of existing 6" sewer pipeline on Giovanni from 6" to 4".

Item No. 3: Revise the following quantities on bid forms:

Bid Item 16 – 6" Sanitary Sewer Pipe (SDR-26): Change Quantity to 180.
Bid Item 17 – 4" Sanitary Sewer Pipe (SDR-26): Change Quantity to 10.

Attachments:

This addendum has been prepared under the direction of the following registered Civil Engineer:



A handwritten signature in black ink that reads "James W. Fisher".

_____ 6/16/2026
James W. Fisher, P.E. Date

Acknowledgment:

I have reviewed the materials included in Addendum 1 to the Giovanni Road Sewer Line Replacement Project and understand the information provided is included as part of the Special Provisions, Proposal and Contract.

By: _____
Bidder's Signature Date

Bidder's Name (printed)

Name of Company