



City of Placerville

Engineering Department

3101 Center Street, Placerville, CA 95667

(530) 642-5250 / (530) 642-5568 fax

ADDENDUM NUMBER 1

Dated: May 15, 2023

**to the
Notice to Bidders, Special Provision, Proposal and Contract Documents
for Construction of**

HOCKING STREET SEWER MAIN REPLACEMENT PROJECT NO. 42245 City of Placerville

Bids Due: Thursday, May 18, 2023; 2:00 p.m.

City Clerk (or designated representative) at City Hall, who will receive at
3rd Floor Engineering Department
3101 Center Street, Placerville, CA 95667
(530) 642-5250

This Addendum is issued to the Hocking Street Sewer Main Replacement Project. Submit proposals for this work with the understanding and full consideration of this Addendum. The revisions declared in this Addendum are essential parts of the Contract.

Bidders are also directed to sign this Addendum as acknowledged, and attach the complete, signed Addendum to the Proposal.

The following responses to questions asked to date:

Question No. 1: After CIPP lining, can sewer services be restored on 4" pipe?

Answer: Services can be restored from sewer cleanouts. However it is not known if 2815 & 2841 Hocking Street have existing cleanouts. If cleanouts cannot be located, installation of new cleanouts by change order may be considered during construction.

Question No. 2: Is the existing pipe between SSHM-1604 and SSCO-2830 to be concrete capped?

Answer: The pipe will be abandoned as a City main but remain in service as a private service lateral (2826 Hocking), and a flusher branch will be installed in the street per Detail 3, Sheet D1.00.

Question No. 3: How will new service connections be made?

Answer: Connections will be made using electrofusion wye inlets after relaxation period.

Question No. 4: Will service laterals need realignment in private property backyards?

Answer: There are two properties that have structures over the existing sewer connections in the backyards (2868 & 2838 Hocking), which will require realignment of the sewer service lateral.

Question No. 5: Is the backyard sewer main alignment straight for a straight pull or are there turns or angles?

Answer: Assume a straight pull. If there are turns or angles, they will be addressed in the field during construction.

Question No. 6: Will air testing and CCTV inspection be required after main installation?

Answer: Air testing is not required, but video inspection will be required per EID Technical Specification 33 01 30.13 found in Appendix A of the project specifications.

Question No. 7: Fused HDPE leaves a bead inside the pipe at the joint. Will the bead need to be removed?

Answer: Yes, the bead needs to be removed per Section 02345 of the project specifications.

Question No. 8: The 252 LF - 4" lining in Hocking Street is expected to be too long to line in a single run. Could a new manhole be placed at the point repair location after lining is complete?

Answer: A new manhole is not currently included the scope to be placed at the point repair location. Assume a close out pipe will be required to connect the two liners.

Question No. 9: Is the contractor responsible for coordinating access to private properties with the homeowners?

Answer: The homeowners have been contacted by the City regarding the project. Homeowners understand the scope of the project and have been cooperative. The contractor will need to arrange access to private properties during construction. The City will be available to help facilitate coordination with property owners. Preconstruction photos are required to be submitted to the City before working on private properties.

Question No. 10: Is there a staging area?

Answer: The staging area will be on Ferrari Ct on EID property as shown on sheet G0.40 of the project plans. An Agreement to Enter and Stage is included in Appendix C of the plans.

Question No. 11: What is the number of working days?

Answer: 50 days.

Question No. 12: What are the pipe materials of the private service laterals?

Answer: Unknown.

Question No. 13: Can the new service connection be tied in through the same hole that was used for the temporary sewer connection?

Answer: Yes, the same hole will be required to be used.

Question No. 14: Who will be the inspector?

Answer: The inspector will be contracted from Dewberry Engineers for this project and has not yet been determined.

Attachments:
Sign-in Sheet – Pre-Bid Meeting (5/11/2023)

This addendum has been prepared under the direction of the following registered Civil Engineer:

ACSchiestel

A. Cory Schiestel, PE

5/15/2023

Date



Acknowledgment:

I have reviewed the materials included in Addendum 1 to the Hocking Street Sewer Main Replacement Project and understand the information provided is included as part of the Special Provisions, Proposal and Contract.

By: _____
Bidder's Signature Date

Bidder's Name (printed)

Name of Company

HOCKING STREET SEWER MAIN REPLACEMENT PROJECT - PRE-BID MEETING

CITY OF PLACERVILLE - CIP #42245 - 5/11/2023

NAME	COMPANY	PHONE NO.	EMAIL ADDRESS
Cory Schiestel	City of Placerville	(530) 642-5557	cschiestel@cityofplacerville.org
Wes Larrabure	City of Placerville	(916) 642-5567	wlarrabure@cityofplacerville.org
Clif Cox	C. E. Cox Eng, INC.	(916) 995-1959	cecoxeng@comcast.net
Murray Cannedy	Express Sewer & Drain	(916) 855-8639	Murray@expresssewer.com
James Young Gordon Vinci	Joe Vinci inc	530-363-6279	Joe Vinci, INC @ ATT. DIET
Dave Richard	Darhany	(249) 769-5060	drichard@darhany.com